

Panasonic India Techno-Park Project

2016.03.14

NIKKEN SEKKEI Construction Management, Inc.

About NIKKEN SEKKEI Group

Comprehensive professional consultancy group
Providing one-stop service for
a large variety of planning, design and management

- Established in 1900
- Owns 8 specialized subsidiary companies
- More than 2,400 staff
- Completed over 20,000 projects in over 40 countries



About NIKKEN SEKKEI Group



Introduction

1. Project Features

2. Overall Management

3. Main Achievements

Summary

Private Techno-Park for Panasonic

Site area of approximately 300,000m²

Air-Conditioner Factory, Washing Machine Factory,
and Welding Machine Factory

Eco-Friendly Facilities

Laws, Custom, and Standards

Flexibility



1. Project Features

The One and Only for Panasonic

➡ **P**rospective study for site

“Indian Time” Problem

➡ **S**chedule Management

International Competition


➡ **C**ost Management

Glocal and Eco

➡ **Q**uality Control

Site location

5



New Delhi

120 min


India Techno-Park

60 min

Airport

Site Layout


6



Name of Building	Building Area (m ²)	Floor Area (m ²)	Structure	Floor
Office	698.98	1,289.29	RC	2F
Air-conditioner factory	24,018.20	25,179.52	S	2F
Washing machine factory	11,887.97	11,887.97	S	1F
Welding machine factory	8,275.68	9,686.78	S	2F
others	1,766.39	1,766.39	RC/S	1F
Total	46,647.22	49,809.95	—	—

Entire View of the Site


7



2. Overall Management

Organizational characteristics

9



NCM's Roles and Responsibilities

10

1. Provide overall project control support for Panasonic FMG
2. Support to create each manufacturing function
3. Guide Panasonic India for land acquisition

1. Research stage for site selection

Survey, soil study, groundwater investigation assistance
Advice on land sales contract

4. Designer/contractor selection stage

Design/construction company prequalification
Preparation of proposal guideline, and implementation/evaluation of proposals

2. Basic plan stage

Identification of requirements by each factory specialized division
Identification of requirements for eco-friendly Techno-Park utilities and infrastructure

5. Design stage

Basic design/detailed design review
Review of estimated construction cost and advice on construction contract

3. Planning stage

Techno-Park master plan formulation
Techno-Park guideline formulation

6. Construction stage

Monitoring of quality and attendance on Client's inspection
Follow-ups (6-month and 1-year inspections)

3. Main Achievements

Development of the most applicable construction site for Panasonic

• Points of Prospective study

- 1) Site storm water drainage gradient
- 2) Access road level
- 3) Site development level
- 4) Surface soil replacement
- 5) Well water quality analysis




Site at the Time of Completion

Prospective study for site


The One and Only for
Panasonic

13

• Site storm water drainage gradient





Site Storm water Drainage Gradient Study Drawing



3-D Site Survey Map

• Access road level




Access route study map

Prospective study for site

The One and Only for
Panasonic

14

• Surface soil replacement and Well water quality analysis




Site Vicinity Underground Water Study Materials



Soil Investigation for the Site's Surface Layer


Making up for the delay of the CLU application process



Schedule Management

“Indian Time” Problem

16



- Various risks in India which might cause delay

Time Lags Between Indian and Japanese

Long Absence During Diwali (The Indian New Year holiday)

High Temperature (Around 50°C)

Rainy Season (From July To September)

- Shortening the construction periods

1) Early Roofing Before Floor Slab

2) Overlapping Construction and Installation Phases



Schedule Management

“Indian Time” Problem

19

• Opening Ceremony on “Triple Twelve”



2012/12/12 “Triple Twelve”






Pre-Qualification Screening

Creation of a Fair Competition

[illegible][illegible]

• Result of International Competition

The largest Contractor in India



- Points of Cost Management

1) Clear Rules for Design Changes

Limit Total Cost

Fix Unit Prices

2) Against Price Hike in India

Steel Frame Ordered in Advance

Publicly-Available Indicators




Steel Frame Ordered in Advance

- Price hike in India

Price Hike
50 points up



Steel Frame Ordered in Advance



**Design Build Contractor
Evaluation**

Commencement

Completion

**Environmental Friendliness and Response to the
Characteristics of India**



Realization of Eco-Friendly Techno-Park

Guidelines for Panasonic Global Quality

Specifications Respecting Local Condition

• Eco-Friendly Facilities


Wastewater reuse (water treatment)

Rainwater infiltration tank


Photovoltaic facilities

Solar water heating facilities

Skylights for reducing daytime lighting



Underground Water Use 178 KL/day
Recycled Water Use 174 KL/day



- Design Guidelines for Panasonic Global Quality

Flow line rules for the road


Concept for common infrastructure

Ratio of green area required

Setback rules for each block

Security rules within the premise

Unification of specifications for rooms.



- Various measures to adapt for India

Indian Climate Conditions

Usual Familiar Method

Global Quality



Brick wall & Rich insulation

Wet joint Method

Dry joint Method



The One and Only for Panasonic

“Indian Time” Problem

International Competition

Glocal and Eco

**Flexibility
For
Global Projects**



Safety Prayer Ceremony rooted in the Local Culture

END